No.	Items or work	Store rooms		Latrines	
		Per	Quantity	Per	Quantity
43	Providing pillars, capitals, and dome of end towers complete ...	...	...	Each	8
44	Forming bases and capitals of half pillars in front and rear of end wings.	...	...	"	16
45	Forming nitches foliation and plastering introdas of arches ⅜" deep of end wings front and rear.	...	...	"	22
46	Forming and plastering the foliation of centre block front and rear ...	...	...	"	2
47	Cornice 6" top of ventilators	...	...	R. ft.	100
48	Burnt stones brackets including plastering	...	...	Each	237
49	Cuddappah slabs lovey 2"	...	...	S. ft.	922
50	Constructing vimanams of end wings	...	...	Each	4
51	Brick in chunam plain parapet plastering (1½×1½) binding wall ...	...	...	R. ft.	38
52	Ornamental parapet wall 3 feet high including pedastals and plastering	...	...	"	677
53	Zinc spouts 4" diar.	...	...	"	80
54	Teakwood panelled screens for partition	S. ft.	1,785	S. ft.	2,212

CONSTRUCTING STORE ROOMS, AND LATRINES OF SIX SEATS.

No.	Items of work	Store rooms		Latrines	
		Per	Quantity	Per	Quantity
1	Earthwork excavating and refilling basement	C. yd.	300	C. yd.	12
2	Stone jelly concrete	C. ft.	3,540	C. ft.	244
3	Burnt brick in chunam foundation and basement... ...	"	4,578	"	254
4	Brick in chunam superstructure	"	9,718	"	450
5	Do arch work	"	97	Nil	Nil
6	Burnt stone slabs roughly dressed	S. ft.	519	Nil	Nil
7	Plastering with chunam mortar	Sqr.	176·40	Sqr.	6·97
8	Teakwood doors panelled, complete	S. ft.	300	S. ft.	20
9	Teakwood windows with iron bars, etc., complete	"	261	Nil	Nil
10	Teakwood ventilators with glazed shutters, etc.	"	192	Nil	Nil
11	Teakwood shutters of arch way	"	402	Nil	Nil
12	Flooring with burnt stone slabs of 3" over sand	Sqr.	9·00	Sqr.	1·20
13	Flooring with Cudappah slab over 3" concrete and cement pointing ...	Sqr.	27·00	Nil	Nil
14	Madras old steel rail 22 feet long at Rs. 1½	Each	3	Nil	Nil
15	Teakwood work wrought and put up including oiling	C. ft.	519·0	Nil	Nil
16	Roofing with 1st class Mangalore Tiles over teak reepers and complete	Sqr.	75·69	Nil	Nil
17	Ridge tiles set in mortar	R. ft.	319	Nil	Nil
18	Chunam Borders	"	172	Nil	Nil
19	Teakwood shelf 1½" planks, pegs, etc.	S. ft.	405	Nil	Nil
20	Teakwood ornamental eave board	R. ft.	724	Nil	Nil
21	Teakwood finials big	Each	6	Nil	Nil
22	Do small pendants	"	20	Nil	Nil
23	White and colour washing	Sqr.	176·40	Nil	Nil
24	Painting doors and windows	"	34·00	Nil	Nil
25	Levelling ground and clearing site	Lump	sum	Nil	Nil
26	Burnt stone slabs 6" thick one line dressed	Nil	Nil	S. ft.	191
27	Curb stone dressed and top rounded off and fixed	Nil	Nil	R. ft.	22
28	Cement plastering ½" thick	Nil	Nil	Sqr.	8·97
29	Coping with brick in mortar 6" thick and plastered	Nil	Nil	R. ft.	36
30	Teakwood shutters 1" thick planks with frames and hinges, etc., complete.	Nil	Nil	S. ft.	68
31	Concrete drain 3"×6" and cement pointing	Nil	Nil	R. ft.	76
32	Roofing with stone slabs 3" thick laid flat with 3" concrete plastered over and pointed with cement cieling.	Nil	Nil	Sqr.	1·34
33	Buckets in latrines	Nil	Nil	No.	6
34	Iron tub cistern	Nil	Nil	"	1
35	Granalothic flooring of cement concrete	Nil	Nil	Sqr.	·63
36	Making holes in slabs of latrine	Nil	Nil	No.	6
37	Cement concrete for latrine floor	Nil	Nil	C. ft.	14
38	Tarring and white washing, etc., complete	Lump	sum	Lump	sum
39	Iron shutters in rear with iron work, clamps, etc., complete... ...	Nil	Nil	S. ft.	18
40	Plain cornice	Nil	Nil	R. ft.	55
	Constructing Compound Wall.				
1	Earth work excavation	C. yd.	37	Nil	Nil
2	Concrete for filling foundation	C. ft.	337	Nil	Nil
3	Burnt brick in mortar for foundation and basement	"	1,092	Nil	Nil
4	Super-structure burnt brick in mud	"	932	Nil	Nil
5	Coping with brick in mud with chunam plastering	R. ft.	426	Nil	Nil
6	Chunam plastering	S.qr.	50·53	Nil	Nil
7	Gate pillars	Lump	sum	Lump	sum

T. LAKSHMANA RAO,
Chairman.

MYSORE DIVISION.

Absract Notification.

The attention of the public is invited to the notification, dated published in the extenso on page 84, Part IV of the *Mysore Gazette*, dated 1st February 1917, calling for tenders for Improving Staff Quarters at Mysore.

S. H. LAKSHMINARASAPPA,
Assistant Engineer,
Headquarter Range, Mysore.